



CTH G-33

STH 96 to CTH V

Description & Justification:

- Pavement Rating: Varies between 3 and 4 (out of 10)
- Project Length: 4.75 miles
- The existing two-lane roadway will have 2-inches of asphalt milled and 2.5-inches of new asphalt placed.
- The finished two-lane roadway will consist of 12 foot lanes and 5 foot paved shoulders.
- The road will remain open to traffic during paving operations—reduced to one lane in each direction with flaggers.
- The project will be resurfaced by the Brown County Public Works Department.
- Resurfacing is anticipated to begin in April 2018.



2018 Surface Maintenance